
Design goals

Output: Input: 2e8 antiprotons every 2 seconds 2e8 antiprotons every 2 seconds 320 π mm mr (95% unnormalized) 45 π mm mr (95% unnormalized) ∂p = 60 MeV/c (95%) ∂p = 6 MeV/c (95%)

Density Increase 500x Factor of 10 longitudinal Factor of 7 both transverse planes



Debuncher Cooling Performance

Paul Derwent, David Mcginnis, Ralph Pasquinelli, David Vander Meulen, Steve Werkema Fermi National Accelerator Laboratory, P.O. Box 500, Batavia, IL USA 60510-0500

We present measurements of the Fermilab Debuncher momentum and transverse cooling systems. These systems use liquid helium cooled slotted waveguide pickups and slotted waveguide kickers covering the frequency range 4-8 GHz.

Measure: For le8 particles Longitudinal: Factor of 12.8 in 2 seconds limited by asymptotic width, not rate

Transverse: Factor of 17 in 2 seconds expect factor ~12 with 2e8 particles as limited by available power

Abstract:

